



Ken Robbins
Highway Administrator

702 K St.
Belleville, KS 66935
Phone: (785) 527-2235
Fax: (785) 527-5335

Weekly Report to Commissioners

Community Concerns

Culvert Installation/Replacement Requests:

- 230 Road .25 miles north of Narka (SE corner of the NE Quarter Section 16), a new 60ft driveway is requested directly across from an agricultural building and existing 60ft driveway.

Other Concerns:

- 80 Road .5 miles south of Shady Road on the west side; trees/brush need to be removed from the right-of-way.
- Penn Road, east of Scandia on the south side; trees/brush need to be removed from the right-of-way.
- 20 Road between Queen and Rock Road, improvements are needed. Water is ponding on the road.

High Banks Wind Energy Project activities

The County has assumed maintenance on all project roads. The Developer's improvements within the County Right-of-Ways are substantially complete. An Engineer has completed an inspection of all roads and structures in the project. Punch lists, noting deficiencies have been compiled by the Engineer for Motor Grader Districts 4,5,9 & 10. A post construction meeting with the Developer is scheduled for May 14, 2024.

Department Reports on Non-Routine Activities

Roads and Bridges

- Draft Budgets were prepared for 2025 Roads & Bridges, Solid Waste, Transportation and Weed Departments.
- 2 Applicants are being considered for the Spayer Operator/Truck Driver Position.
- A preconstruction meeting is being scheduled on May 6 April for the replacement of Bridge X-19.1 south of Talmo. Construction is expected to begin in June.

PENDING ACTIONS IN RESPONSE TO COMMUNITY CONCERNS

Bridge and Culverts Division Project List (in order of priority)

1. Norway Lane: drainage improvements are needed.
2. 50 Road 1.4 miles south of KS148; a 24" Concrete tile culvert is separating under the shoulder of the road and needs to be replaced.

Roads and Driveways Division Project List (in order of priority)

1. 110 Road .5 miles south of US36 on the west side; a new house will be moved to this location in July and a driveway is needed. *Completed*
2. 230 Road .5 miles south of Hickory Road on the west side; the property owner needs a driveway culvert replaced. *Completed*
3. Valley Road .3 mile east of Talmo Lane on the north side; a 20ft driveway needs to be widened to 40ft.
4. Jade Road .3 mile west of 300 Road on the west side; a driveway needs improved with a 30' x 18" culvert.
5. 30 Road .5 mile north of Elm Road on the west side; skewed driveway for grain bins is the low spot in a very shallow watershed. The property owner is seeking improvements that may include ditch cleaning or a lift on the road or driveway, or a culvert.
6. Rock Road between 30 & 50 Roads; a regrade, ditch cleaning and improved gravel finish may be necessary.
7. Queen Road east of 260 Road for the 1st quarter mile; trees and brush need to be cleared from the right-of-way on both sides of the road.
8. Gravel is requested for a half mile of Diamond Road west of 310 Road. *This work will be performed with reclaimed material from the wind farm project when it becomes available soon.*
9. Residents north of Fir Road on Republic Lane are requesting improvement of the road base with larger gravel or rock. The fine sand common to the area becomes tracked up easily when it is wet.
10. 210 Road south of Nickel; .1 mile is graveled from Nickel to a residence and .6 mile is graveled from US 36 north. A resident is requesting that the remaining .3 mile be graveled for direct access to Nickel where a number of residents live.
11. 100 Road .28 mile south of Timber Road on the west side; a 30" squash crossroad pipe has been cleaned out transferring runoff from acreage on the east side to a shallow ditch on the west side that cannot get through a plugged culvert several hundred feet to the south. The farmer believes most of the runoff could stay on the west side with some ditch cleaning. *investigating*
12. Queen Road, west of 20 Road, tree removal, ditch cleaning and driveway upgrades needed for the first .5 mile. *40 ft driveway installed; some ditch cleaning still needed.*
13. 30 Road improvements to restore the crown in the roadway between Highway 36 and Fir Road. *4 miles have been completed.*
14. Fir Road, east of residence at 2641, ditch work needed to re-route drainage out of field and a damaged culvert replaced.
15. 30 Road south of Bridge 3-D.7 and north of Elm Road, ditch cleaning is needed and a road lift.
16. *70 Road south of US 36 Highway has been prepared to receive recycled asphalt paving. A schedule and cost sharing plan for Paving will be prepared by the Highway Administrator for the Commission and Property Owners to consider.*
17. Cut and patch 4-6ft of Concrete at 170 Road near residence 1549 (*Primary Road; Currently 23x23 & 10x23 inch potholes where previous asphalt patch has failed*). *A hot asphalt patch is being tested at this location.*

Upcoming Events

1. The Kansas Department of Transportation is currently accepting proposals for the following programs:
 - Federal Fiscal Year 2026 Off-System Bridge Program (OSB)
 - State Fiscal Year 2025 Kansas Local Bridge Improvement (KLBIP)Applications for both programs must be received by May 24, 2024.
2. U.S. Senator Roger Marshall, M.D. announced \$1,520,000 in grant funding to the North Central Regional Planning Commission from the U.S. Department of Transportation's Safe Streets and Roads for All (SS4A) grant program.
 - a. *The Highway Administrator is communicating with the North Central Region Planning Commission (NCRPC) about what this means for Republic County. Representatives for the NCRPC do not know yet but hope to bring all the member counties together within the next 60-90 days to consider next steps.*
3. Special Projects in the works or being considered by the Highway Administrator
 - a. Asphalt paving options.
4. Vacations of Right-of-Ways are proposed for 3 road spurs adjacent to Highway 81 that were abandoned after improvements to the Highway many years ago.